PLAN

## NOTES:

BRICK MASONRY CAN BE COMMON CLAY BRICK, JUMBO BRICK, OR CONCRETE BRICK.


CONCRETE BOTTOMS SHALL BE PAID AS BRICK MASONRY.

ALL MORTAR JOINTS ARE TO BE 1/2" ± 1/8".

CONCRETE COVER TO BE PAID FOR UNDER THE PAY ITEM 4'X4' PRECAST CONCRETE YARD INLET COVER.

FOR DEPTHS OVER 4'-0" USE STEPS ON 16" CENTERS. STEPS SHALL BE IN ACCORD-ANCE WITH COG STD. #414.

FOR PRECAST CONCRETE MODELS OF THIS STRUCTURE, THE MANUFACTURER SHALL STAMP OR STENCIL ITS LOGO OR NAME ON THE INSIDE AND OUTSIDE OF THE STRUCTURE.



DEDUCTIONS FOR ONE PIPE			
PIPE SIZE	C. M.	R.C.	
12"	0.020	0.032	
15"	0.031	0.047	
18"	0.044	0.065	

## SECTION A-A

QUANTITIES			
BASE (C. Y.)	H(PER FT. HEIGHT)	PIERS (C.Y. EACH)	
0.296	0.330	0.006	

## CITY OF GREENSBORO

STANDARD 4' X 4' BRICK MASONRY YARD INLET 

 STD. NO.
 REV.

 424
 08-02 12-07